

ADDENDUM No. 3  
TO THE  
CONTRACT DOCUMENTS FOR CONSTRUCTION OF  
FULTON SHOP BUILDING REROOF  
PROJECT No. 22PW07

THIS ADDENDUM IS HEREBY MADE A PART OF THE CONTRACT DOCUMENTS DATED  
March 14, 2022, TO THE SAME EXTENT AS THOUGH IT WERE ORIGINALLY INCLUDED  
THEREIN.

ISSUED THIS 7th DAY OF April, 2022.

CITY OF ROSEBURG  
PUBLIC WORKS DEPARTMENT  
900 SE DOUGLAS AVENUE  
ROSEBURG, OREGON 97470  
(541) 492-6730

This addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated March 14, 2022 as noted below. Acknowledge receipt of this addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

**GENERAL INFORMATION:**

1. Addendum #1 was issued on March 25, 2022
2. Addendum #2 was issued on March 31, 2022

**CONTRACT DOCUMENTS and SPECIFICATIONS:**

1. Bid Form
  - a. Add "Additive" to each alternate.
2. Section 07 5400 – Thermoplastic Membrane Roofing
  - a. 2.2 Thermoplastic Membrane Roofing and Associated Materials
    - Item C.2 – Material: Add item b. to read:  
  
"b. Poly Vinyl Chloride (PVC) roofing complying with ASTM D4434 is acceptable"

**DRAWINGS:**

1. Sheet A121 – Roof Plan – West
  - a. Keynote 54. Change pipe size from "6" Dia..." to "4" Dia..."
2. Sheet A122 – Roof Plan – East
  - a. Keynote 54. Change pipe size from "6" Dia..." to "4" Dia..."
3. Sheet A161 – Details
  - a. Detail 1
    - Add note that reads:  
"NOTE: ROOF DRAIN TO BE JR SMITH ROOF DRAIN 1010 WITH LOW PROFILE DRAIN. PIPING TO BE 4" DIAMETER PVC. SEE SCOPE OF WORK NOTE Q ON SHEET A120 – ROOF PLAN – OVERALL FOR ADDITIONAL ROUTING INFORMATION."
4. Sheet A162 - Details
  - a. Detail 8
    - Add note that reads:  
"NOTE: ROOF DRAIN TO BE JR SMITH ROOF DRAIN 1010 WITH LOW PROFILE DRAIN. PIPING TO BE 4" DIAMETER PVC. SEE SCOPE OF WORK NOTE Q ON SHEET A120 – ROOF PLAN – OVERALL FOR ADDITIONAL ROUTING INFORMATION."

**END OF ADDENDUM NO. 3**

  
Ryan Herinckx  
Project Manager  
Issued April 7, 2022